

TIREMAAX®

Thermoplastic Tire Hoses

The below chart summarizes the standard TIREMAAX Thermoplastic Tire Hose part numbers by wheel combination, length and identification label color.


HOSE STYLE	WHEEL STYLE	TIRE SIZE	WHEEL MATERIAL	POSITION	FITTING	PART NO.	LENGTH "L"	ID LABEL COLOR
Standard	Dual	***17.5"	Alum, Steel or Combo	Inner	Straight	VS-33767-7	12.0"	Cyan
				Outer	180-Degree	VS-33769-4	8.8"	Light Green
		19.5"	Alum	Inner	Straight	VS-33767-7	12.0"	Cyan
				Outer	180-Degree	VS-33769-3	9.6"	Tan
			Steel or Combo	Inner	Straight	VS-33767-2	14.5"	Blue
				Outer	180-Degree	VS-33769-3	9.6"	Tan
		22.5"	Alum	Inner	Straight	VS-33767-5	14.0"	Pink
				Outer	180-Degree	VS-33769-1	11.0"	White
			Steel or Combo	Inner	Straight	VS-33767-1	15.5"	Green
				Outer	180-Degree	VS-33769-1	11.0"	White
			*Alcoa ULT36 All Alum	Inner	Straight	VS-33767-2	14.5"	Blue
				Outer	110-Degree	VS-41701-1	10.3"	Yellow
			*Alcoa ULT36 Steel Combo	Inner	Straight	VS-33767-1	15.5"	Green
				Outer	110-Degree	VS-41701-1	10.3"	Yellow
		24.5"	Alum	Inner	Straight	VS-33767-2	14.5"	Blue
				Outer	180-Degree	VS-33769-2	12.6"	Orange
			Steel or Combo	Inner	Straight	VS-33767-1	15.5"	Green
				Outer	180-Degree	VS-33769-1	11.0"	White
	Super Single	22.5"	**Alum	Outward Facing Stem	Straight	VS-33767-6	9.3"	Purple
			Steel	Outward Facing Stem	Straight	VS-33767-3	11.2"	Red
				Inward Facing Stem	180-Degree	VS-33769-1	11.0"	White
Integral Check Port - 1-Port	Dual	22.5"	Alum	Inner	Straight	VS-40176-2	14.0"	Pink / White Stripe
				Outer	180-Degree	VS-40177-1	11.7"	Grey / White Stripe
			Steel or Combo	Inner	Straight	VS-40176-3	16.0"	Green / White Stripe
				Outer	180-Degree	VS-40177-1	11.7"	Grey / White Stripe
			*Alcoa ULT36 All Alum	Inner	Straight	VS-40176-4	15.0"	Blue / White Stripe
				Outer	110-Degree	VS-41748-1	11.8"	Yellow / White Stripe
			*Alcoa ULT36 Steel Combo	Inner	Straight	VS-40176-3	16.0"	Green / White Stripe
				Outer	110-Degree	VS-41748-1	11.8"	Yellow / White Stripe
	Super Single	22.5"	**Alum	Outward Facing Stem	Straight	VS-40176-5	9.3"	Purple / White Stripe
			Steel	Outward Facing Stem	Straight	VS-40176-1	11.7"	Red / White Stripe
				Inward Facing Stem	180-Degree	VS-40177-1	11.7"	Grey / White Stripe
Integral Check Port - 2-Port	Dual	22.5"	Alum	Inner	Straight	VS-41546-2	14.0"	Pink / White Stripe
				Outer	180-Degree	VS-41547-1	11.7"	Grey / White Stripe
			Steel or Combo	Inner	Straight	VS-41546-3	16.0"	Green / White Stripe
				Outer	180-Degree	VS-41547-1	11.7"	Grey / White Stripe
			*Alcoa ULT36 All Alum	Inner	Straight	VS-41546-4	15.0"	Blue / White Stripe
				Outer	110-Degree	VS-41749-1	11.8"	Yellow / White Stripe
			*Alcoa ULT36 Steel Combo	Inner	Straight	VS-41546-3	16.0"	Green / White Stripe
				Outer	110-Degree	VS-41749-1	11.8"	Yellow / White Stripe
	Super Single	22.5"	**Alum	Outward Facing Stem	Straight	VS-41546-5	9.3"	Purple / White Stripe
			Steel	Outward Facing Stem	Straight	VS-41546-1	11.7"	Red / White Stripe
				Inward Facing Stem	180-Degree	VS-41547-1	11.7"	Grey / White Stripe

* Hendrickson recommends grommets in each hand hole of the ULT36 wheel (ref VS-41770)


** For aluminum zero-offset wheels with outward facing stem contact Hendrickson Engineering for applications support

*** For 17.5" wheels with CDHP hubcaps on aluminum hubs, contact Hendrickson Engineering for applications support. 17.5" wheels with CDHP hubcaps on aluminum hubs use VS-33767-4 & VS-33769-3 hoses.

FITTING



HOSE STYLE




*Actual product performance may vary depending upon vehicle configuration, operation, service and other factors.
All applications must comply with applicable Hendrickson specifications and must be approved by the respective vehicle manufacturer with the vehicle in its original, as-built configuration.
Contact Hendrickson for additional details regarding specifications, applications, capacities, operation, service and maintenance instructions.*

Call Hendrickson at 866.RIDEAIR (743.3247) for additional information.



www.hendrickson-intl.com



TRAILER COMMERCIAL VEHICLE SYSTEMS
2070 Industrial Place SE
Canton, OH 44707-2641 USA
866.RIDEAIR (743.3247)
Fax 800.696.4416

HENDRICKSON CANADA ULC
2825 Argenta Road, Unit #1 - 4
Mississauga, ON Canada L5N 8G6
800.668.5360
905.789.1030 • Fax 905.812.9423

HENDRICKSON MEXICANA
Circuito El Marqués Sur #29
Parque Industrial El Marqués
Pob. El Colorado, Municipio El Marqués,
Querétaro, México C.P. 76246
+52 (442) 296.3600 • Fax +52 (442) 296.3601

L1347 Rev C 10-25

© 2015 - 2025 Hendrickson USA, L.L.C. All Rights Reserved. All trademarks shown are owned by Hendrickson USA, L.L.C., or one of its affiliates, in one or more countries. Information contained in this literature was accurate at the time of publication.
Product changes may have been made after the copyright date that are not reflected. Printed in United States of America